OVERFLOW

OVERHEAD

PEDESTRIAN

PARKING METER

POINT ON CURVE

POINT OF TANGENT

POWER POLE

PAVEMENT

ROOF DRAIN

RIGHT-OF-WAY

SLOPE (FT/FT)

STORM DRAIN

SANITARY SEWER

PRIVATE

SHEET

STREET

STATION

STANDARD

SIDEWALK

TOP OF CURB

TRENCH DRAIN

TRANSFORMER

UNDERGROUND

WATER METER WATER VALVE

UNDERGROUND ELECTRIC

TOP OF STAIR

TOP OF WALL TOP OF WALK

TYPICAL

TOP OF GROUND

TOP OF PAVEMENT

PROPERTY LINE

POINT OF CURVATURE

POINT OF CURB RETURN

POST INDICATOR VALVE

POINT OF COMPOUND CURVATURE

POINT OF REVERSE CURVATURE

PUBLIC UTILITY EASEMENT

POLYVINYL CHLORIDE

STORM DRAIN MANHOLE

SANITARY SEWER MANHOLE

OVH/OH

PCR

PED

PIV

PM

POC

P.U.E

PVC

PVMT

SDMH

SHT

SSMH

STA


STD

UG

Baysinger

Baysinger Partners Architecture Portand, OR 97217 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE **STARBUCKS**




PK21052 06.21.2023 Drawn/Check By:


©2022 Baysinger Partners Architecture **PROPOSED** PHASE 2

COVER SHEET

DESIGN REVIEW

BEAVERTON, OR





VICINITY MAP

MAP FROM: GOOGLE MAPS ©

PROJECT INFORMATION

THE PROJECT IS LOCATED AT 10910 SW BARNES ROAD PORTLAND, OR 97225 WITH STATE ID 1S103A001600, TOWNSHIP 1S, RANGE 1W, SECTION 3 LOT 1600, AND IS PART OF THE 1994-109 PARTITION PLAT, LOT 2. ONLY THIS ONE TAX LOT IS AFFECTED BY THIS DEVELOPMENT.

THE ASSOCIATED LAND USE NUMBER IS DR2022-0008

PERVIOUS AND IMPERVIOUS SURFACE AREA

	PERVIOUS AREA (SQFT)	IMPERVIOUS AREA (SQFT)
WITHIN PUBLIC ROW	0	17
PRIVATE PROPERTY	15,045	108,872

PROJECT CONTACTS

PETERKORT TOWNE SQUARE LLC 9755 SW BARNES ROAD, SUITE 690 PORTLAND, OREGON 97225 TEL: 503-292-1981 CONTACT: LOIS D. DITMARS

CIVIL ENGINEER:

FROELICH ENGINEERS, INC. 17700 SW UPPER BOONES FERRY ROAD SUITE 115 PORTLAND, OREGON 97224 TEL: 503-624-7005 CONTACT: EVAN EYKELBOSCH, PE

ARCHITECT:

BAYSINGER PARTNERS ARCHITECTURE 2410 N LOMBARD ST PORTLAND, OREGON 97217 TEL: 503-546-1600

CONTACT: MATTHEW LILLARD, AIA

SHEET LIST TABLE

ABBREVIATIONS

AD

BLDG

BOW

CO

CONC.

COTG

D/W

DIA.,Ø

FDC

O.D

EXIST./EX

APPROX

ASPHALT CONCRETE

AREA DRAIN

BOLLARD

BUILDING

APPROXIMATE

BACK OF WALK

BOTTOM OF SWALE

BOTTOM OF STAIR

CONCRETE MASONRY UNIT

FIRE DEPARTMENT CONNECTION

FINISH FLOOR ELEVATION

HANDICAP PARKING SPACE

CLEANOUT TO GRADE

CONTROL POINT

DUCTILE IRON PIPE

BOTTOM OF WALL

CATCH BASIN

CENTERLINE

CLEANOUT

CONCRETE

DRIVEWAY

DIAMETER

EASTING

EXISTING

FINISH GRADE

FIRE HYDRANT

FOUNDATION

GRADE BREAK

GATE VALVE

HIGH POINT

IRRIGATION

LIGHT POLE

MANHOLE

MINIMUM **NORTHING**

INSIDE DIAMETER

INVERT ELEVATION

OUTSIDE DIAMETER

FLOWLINE

GUTTER

GAS LINE

HEIGHT

SHEET NUMBER	SHEET TITLE
C0.1	COVER SHEET
C1.0	NOTES
C1.1	EXISTING CONDITIONS
C1.2	DEMOLITION PLAN
C2.0	SITE PLAN
C2.1	STATION PLAN
C3.0	GRADING PLAN
C3.1	GRADING PLAN
C3.2	GRADING ENLARGEMENT
C3.3	GRADING ENLARGEMENT - ADA RAMP
C4.0	UTILITY PLAN
C4.1	UTILITY ENLARGEMENTS
C4.2	UTILITY STRUCTURE TABLE
C4.3	FIRE PROTECTION PLAN
C5.0	TYPICAL DETAILS
C5.1	TYPICAL DETAILS
C5.2	TYPICAL DETAILS
C5.3	TYPICAL DETAILS
C5.4	TYPICAL DETAILS
C5.5	TYPICAL DETAILS
C5.6	TYPICAL DETAILS
C6.0	EROSION AND SEDIMENT CONTROL COVER SHEET
C6.1	CLEARING AND DEMOLITION EROSION CONTROL PLAN
C6.2	SITE AND UTILITY EROSION CONTROL PLAN
C6.3	VERTICAL CONSTRUCTION EROSION CONTROL PLAN
C6.4	FINAL STABILIZATION PLAN
C6.5	EROSION CONTROL DETAILS

Plotted: 10/4/23 at 1:56pm By: eeykelbosch

021/21-C023 (Peterkort Towne Square - Starbucks)\300 Document Development - Froelich\302 CAD\PLOT\21-C023-C1.0_COVR.dwg TAB:C1.0

GENERAL NOTES

- 1. SURVEY PROVIDED BY S&F LAND SERVICES, DATED 07/20/2022. ELEVATIONS ARE BASED ON WASHINGTON COUNTY VERTICAL DATUM ESTABLISHED PER BENCH MARK NO. 781 WITH AN ELEVATION OF 350.410'.
- 2. CONSTRUCTION LAYOUT (ALL ACTUAL LINES AND GRADES) SHALL BE STAKED BY A PROFESSIONAL SURVEYOR, REGISTERED IN THE STATE OF OREGON, BASED ON COORDINATES, DIMENSIONS, BEARINGS, AND ELEVATIONS, AS SHOWN, ON THE PLANS.
- 3. PROJECT CONTROL SHALL BE FIELD VERIFIED AND CHECKED FOR RELATIVE HORIZONTAL POSITION PRIOR TO BEGINNING CONSTRUCTION LAYOUT. SEE SHEET C2.0 FOR PROJECT CONTROL INFORMATION.
- 4. PROJECT CONTROL SHALL BE FIELD VERIFIED AND CHECKED FOR RELATIVE VERTICAL POSITION BASED ON THE BENCHMARK STATED HEREON, PRIOR TO BEGINNING CONSTRUCTION LAYOUT.
- 5. WHEN DIMENSIONS AND COORDINATE LOCATIONS ARE REPRESENTED DIMENSIONS SHALL HOLD OVER COORDINATE LOCATION. NOTIFY THE CIVIL ENGINEER OF RECORD IMMEDIATELY UPON DISCOVERY.
- 6. BUILDING SETBACK DIMENSIONS FROM PROPERTY LINES SHALL HOLD OVER ALL OTHER CALLOUTS. PROPERTY LINES AND ASSOCIATED BUILDING SETBACKS SHALL BE VERIFIED PRIOR TO CONSTRUCTION LAYOUT.
- 7. CONTRACTOR SHALL PRESERVE AND PROTECT FROM DAMAGE ALL EXISTING MONUMENTATION DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND PAYING FOR THE REPLACEMENT OF ANY MONUMENTS DAMAGED OR REMOVED DURING CONSTRUCTION. NEW MONUMENTS SHALL BE REESTABLISHED BY A LICENSED SURVEYOR.
- B. EXISTING CONDITIONS MAY NOT BE COMPLETE OR ACCURATE. CONTRACTOR TO VERIFY EXISTING SITE CONDITIONS PRIOR TO CONSTRUCTION. CONTRACTOR SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF THE ENGINEER PRIOR TO BEGINNING CONSTRUCTION.
- 9. ALL CONSTRUCTION AND MATERIALS SHALL CONFORM TO THESE PLANS, THE PROJECT SPECIFICATIONS AND THE APPLICABLE REQUIREMENTS OF THE 2021 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION, THE 2021 OREGON PLUMBING SPECIALTY CODE AND REQUIREMENTS OF THE CITY OF BEAVERTON.
- 10. THE COMPLETED INSTALLATION SHALL CONFORM TO ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES, ORDINANCES AND REGULATIONS. ALL PERMITS, LICENSES AND INSPECTIONS REQUIRED BY THE GOVERNING AUTHORITIES FOR THE EXECUTION AND COMPLETION OF WORK SHALL BE SECURED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION.
- 11. ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503) 232-1987). EXCAVATORS MUST NOTIFY ALL PERTINENT COMPANIES OR AGENCIES WITH UNDERGROUND UTILITIES IN THE PROJECT AREA AT LEAST 48 BUSINESS-DAY HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS PRIOR TO COMMENCING AN EXCAVATION, SO UTILITIES MAY BE ACCURATELY LOCATED.
- 12. THE LOCATION OF EXISTING UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE FOR INFORMATION ONLY AND ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE. CONTRACTOR SHALL VERIFY ELEVATIONS, PIPE SIZE, AND MATERIAL TYPES OF ALL UNDERGROUND UTILITIES PRIOR TO COMMENCING WITH CONSTRUCTION AND SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF FROELICH ENGINEERS, 72 HOURS PRIOR TO START OF CONSTRUCTION TO PREVENT GRADE AND ALIGNMENT CONFLICTS.
- 13. THE ENGINEER OR OWNER IS NOT RESPONSIBLE FOR THE SAFETY OF THE CONTRACTOR OR HIS CREW. ALL O.S.H.A. REGULATIONS SHALL BE STRICTLY ADHERED TO IN THE PERFORMANCE OF THE WORK.
- 14. TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE IMPLEMENTED. THE CONTRACTOR SHALL ADHERE TO CITY OF BEAVERTON FOR MINIMUM EROSION CONTROL MEASURES. THE ESC FACILITIES SHOWN IN THESE PLANS ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
- 15. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL ROADWAYS, KEEPING THEM CLEAN AND FREE OF CONSTRUCTION MATERIALS AND DEBRIS, AND PROVIDING DUST CONTROL AS REQUIRED.
- 16. CONTRACTOR SHALL MAINTAIN ALL UTILITIES TO BLDG. AT ALL TIMES DURING CONSTRUCTION.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND SCHEDULING ALL WORK WITH THE OWNER.
- 18. NOTIFY CITY INSPECTOR 72 HOURS BEFORE STARTING WORK.

MATERIAL NOTES

- GENERAL: MATERIALS SHALL BE NEW. THE USE OF MANUFACTURER'S NAMES, MODELS, AND NUMBERS IS INTENDED TO ESTABLISH STYLE, QUALITY, APPEARANCE, AND USEFULNESS. PROPOSED SUBSTITUTIONS WILL REQUIRE WRITTEN APPROVAL FROM ARCHITECT PRIOR TO INSTALLATION.
- STORM AND SANITARY SEWER PIPING SHALL BE PVC PIPE, DUCTILE IRON PIPE, OR HIGH DENSITY POLYETHYLENE (HDPE) PIPE CONFORMING TO THE PROJECT SPECIFICATIONS; AS INDICATED IN THE PLANS.
- 3. CONCRETE FOR CURBS, SIDEWALK AND DRIVEWAYS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,300 PSI AT 28 DAYS.

CONSTRUCTION NOTES

GENERAL

- SUBGRADE AND TRENCH BACKFILL SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-1557. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER IS NOT PERMITTED.
- 2. SPECIAL INSPECTION REQUIRED FOR ALL COMPACTION TESTING.

DEMOLITION

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND DISPOSAL OF EXISTING AC, CURBS, SIDEWALKS AND OTHER SITE ELEMENTS WITHIN THE SITE AREA IDENTIFIED IN THE PLANS. DISPOSE OF DEMOLISHED ITEMS OFF-SITE IN A LEGAL MANNER.
- 2. EXCEPT FOR MATERIALS INDICATED TO BE STOCKPILED OR TO REMAIN ON OWNER'S PROPERTY, CLEARED MATERIALS SHALL BECOME CONTRACTOR'S PROPERTY, REMOVED FROM THE SITE, AND DISPOSED OF PROPERLY.
- 3. ITEMS INDICATED TO BE SALVAGED SHALL BE CAREFULLY REMOVED AND DELIVERED STORED AT THE PROJECT SITE AS DIRECTED BY THE OWNER.
- 4. ALL LANDSCAPING, PAVEMENT, CURBS AND SIDEWALKS, BEYOND THE IDENTIFIED SITE AREA, DAMAGED DURING THE CONSTRUCTION SHALL BE REPLACED TO THEIR ORIGINAL CONDITION OR BETTER.
- 5. CONCRETE SIDEWALKS SHOWN FOR DEMOLITION SHALL BE REMOVED TO THE NEAREST EXISTING CONSTRUCTION JOINT.
- 6. SAWCUT STRAIGHT MATCHLINES TO CREATE A BUTT JOINT BETWEEN THE EXISTING AND NEW PAVEMENT.

GRADING

- 1. ALL SURFACES SHALL HAVE MINIMUM 1.5% SLOPE UNLESS OTHERWISE NOTED ON PLANS. ALL SURFACES SHALL MEET EXISTING GRADES SMOOTHLY AND EVENLY AND MAINTAIN CONSTANT SLOPES UNLESS OTHERWISE NOTES ON PLANS.
- 2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING EXISTING SITE AND DRAINAGE PATTERNS AND PROTECTION OF EXISTING ENGINEERED DRAINAGE FACILITIES.
- 3. CONTRACTOR SHALL EXERCISE EXTREME CAUTION WHEN WORKING IN AREAS ADJACENT TO EXISTING TREES IN ORDER TO MINIMIZE DISTURBANCE TO TREE ROOTS. CONTRACT SHALL INSTALL TREE PROTECTION FENCING AS INDICATED ON PLANS OR DRIP-LINE OF EXISTING TREES. NO PARKING VEHICLES UNDER TREES.

<u>UTILITIES</u>

- 1. ADJUST ALL INCIDENTAL STRUCTURES, MANHOLES, VALVE BOXES, CATCH BASINS, FRAMES AND COVERS, ETC. TO FINISHED GRADE.
- 2. CONTRACTOR SHALL ADJUST ALL EXISTING AND/OR NEW FLEXIBLE UTILITIES (WATER, TV, TELEPHONE, ELEC., ETC.) TO CLEAR ANY EXISTING OR NEW GRAVITY DRAIN UTILITIES (STORM DRAIN, SANITARY SEWER, ETC.) IF CONFLICT OCCURS.
- 3. CONTRACTOR SHALL COORDINATE WITH PRIVATE UTILITY COMPANIES FOR THE INSTALLATION OF OR ADJUSTMENT TO GAS, ELECTRICAL, POWER AND TELEPHONE SERVICE.
- BEFORE BACKFILLING ANY SUBGRADE UTILITY IMPROVEMENTS CONTRACTOR SHALL SURVEY AND RECORD MEASUREMENTS OF EXACT LOCATION AND DEPTH AND SUBMIT TO ENGINEER AND OWNER.

STORM AND SANITARY

- 1. CONNECTIONS TO EXISTING STORM AND SANITARY SEWERS SHALL CONFORM TO THE 2021 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION, SECTION 00490, "WORK ON EXISTING SEWERS AND STRUCTURES".
- 2. BEGIN LAYING STORM DRAIN AND SANITARY SEWER PIPE AT THE LOW POINT OF THE SYSTEM, TRUE TO GRADE AND ALIGNMENT INDICATED WITH UNBROKEN CONTINUITY OF INVERT. THE CONTRACTOR SHALL ESTABLISH LINE AND GRADE FOR THE STORM AND SANITARY SEWER PIPE USING A LASER.
- 3. ALL ROOF DRAIN AND CATCH BASIN LEADERS SHALL HAVE A MINIMUM SLOPE OF 2 PERCENT UNLESS NOTED OTHERWISE IN THE PLANS.

WATER

- ALL WATER AND FIRE PROTECTION PIPE SHALL HAVE A MINIMUM 36-INCH COVER TO THE FINISH GRADE.
- 2. ALL WATER AND FIRE PRESSURE FITTINGS SHALL BE FULLY RESTRAINED.
- 3. ALL WATER MAIN / SANITARY SEWER CROSSINGS SHALL CONFORM TO THE OREGON STATE HEALTH DEPARTMENT REGULATIONS, CHAPTER 333.
- 4. ALL WATER LINES SHALL BE THOROUGHLY FLUSHED, CHLORINATED AND TESTED IN ACCORDANCE WITH OREGON STATE HEALTH DEPARTMENT PRIOR TO ANY METER HOOK UP SERVICE.

EARTHWORK

- CONTRACTOR SHALL PREVENT SEDIMENTS AND SEDIMENT LADEN WATER FROM ENTERING THE STORM DRAINAGE SYSTEM.
- 2. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER WILL NOT BE PERMITTED.
- 3. BACKFILL: REFERENCE THE PROJECT SOILS REPORT.
- 4. COMPACTION AND LIFTS: REFERENCE THE PROJECT SOILS REPORT.
- 5. NONWOVEN GEOTEXTILE MIRAFI 140N, OR APPROVED EQUIVALENT

PUBLIC WATER SYSTEMS CONSTRUCTION

- 1. ALL WATERLINE AND APPURTENANCE MATERIALS, INSTALLATION, AND TESTING SHALL MEET TUALATIN VALLEY WATER DISTRICT CURRENT STANDARDS AND SPECIFICATIONS.
- 2. ALL WATERLINE AND FITTINGS SHALL BE ZINC AND ASPHALT COATED, CEMENT MORTAR LINED, AND CLASS 52 DUCTILE IRON PIPE WITH POLYETHYLENE ENCASEMENT.
- 3. ONLY TVWD PERSONNEL CAN OPERATE EXISTING OR HOT TAPPED WATER SYSTEM VALVES.
- 4. THE CONTRACTOR MUST CONTACT A TVWD INSPECTOR AT LEAST 48 HOURS BEFORE ANY WATER SYSTEM CONSTRUCTION TO REQUEST A PRE-CONSTRUCTION MEETING.

SEPARATION STATEMENT

ALL WATER MAIN CROSSINGS SHALL CONFORM TO THE OREGON STATE HEALTH DEPARTMENT, CHAPTER 333. WATER MAINS SHALL CROSS OVER SANITARY SEWERS WITH A 18" MINIMUM CLEARANCE BETWEEN OUTSIDE DIAMETERS OF PIPE WITH ALL PIPE JOINTS EQUIDISTANT FROM CROSSING. HORIZONTAL SEPARATION BETWEEN WATER MAINS AND SANITARY SEWERS IN PARALLEL INSTALLATIONS SHALL BE 10'. MAINTAIN 12" MINIMUM VERTICAL DISTANCE FOR ALL OTHER UTILITY CROSSINGS AND 12" HORIZONTAL PARALLEL DISTANCE. IN CASES WHERE IT IS NOT POSSIBLE TO MAINTAIN THE MINIMUM 10' HORIZONTAL SEPARATION, THE WATER MAIN SHALL BE LAID ON A SEPARATE SHELF IN THE TRENCH 18" INCHES ABOVE THE SEWER.

COMPLIANCE STATEMENT

THIS DESIGN COMPLIES WITH ORS 92.044(7) IN THAT NO UTILITY INFRASTRUCTURE IS DESIGNED TO BE WITHIN 1 FOOT OF A SURVEY MONUMENT SHOWN ON A SUBDIVISION OR PARTITION PLAT. NO DESIGN EXCEPTION OR FINAL FIELD LOCATION CHANGE SHALL BE PERMITTED IF IT WOULD CAUSE ANY UTILITY INFRASTRUCTURE TO BE PLACED WITHIN A PROHIBITED AREA.

NOTICE TO EXCAVATORS:
ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.

(NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503)-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS

Dig | Safely.

Call the Oregon One-Call Center

1-800-332-2344

Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE

STARBUCKS



PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

PROPOSED

©2022 Baysinger Partners Architecture

PROPOSED
PHASE 2
NOTES

C1.0
DESIGN REVIEW

Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

©2022 Baysinger Partners Architecture

PROPOSED

PHASE 2

DEMOLITION

PLAN

C2.0
DESIGN REVIEW

SCALE: 1" = 20'





Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217



mattl@BaysingerPartners.com

503-546-1600



PETERKORT TOWNE SQUARE STARBUCKS



PK21052 Drawn/Check By:

©2022 Baysinger Partners Architecture PROPOSED PHASE 2 SITE

PLAN

DESIGN REVIEW

SCALE: 1" = 20' Plotted: 10/4/23 at 1:57pm By: eeykelbosch

PETERKORT TOWNE SQUARE STARBUCKS


PK21052 06.21.2023 BLU/EME Drawn/Check By:

PROPOSED PHASE 2 STATION PLAN

©2022 Baysinger Partners Architecture

DESIGN REVIEW

1 INCH = 20 FEET



STATION AND STRIPING PLAN SCALE: 1" = 20'

Plotted: 10/4/23 at 1:57pm By: eeykelbosch

Plotted: 10/4/23 at 1:57pm By: eeykelbosch



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com



FROELICH

ENGINEERS

STRUCTURAL

Portland, OR. | Bend, OR. | Denver, CO. (503) 624-7005

PETERKORT TOWNE SQUARE STARBUCKS

Revisions

PK21052

Original Issue: 06.21.2023

Orawn/Check By: BLU/EME

© 2022 Baysinger Partners Architect
PROPOSED
PHASE 2

GRADING PLAN

C3.0
DESIGN REVIEW

SHEET NOTES

 SLOPES PROVIDED ON SLOPE ARROW ARE FOR REFERENCE ONLY.

2. LANDINGS ON ACCESSIBLE ROUTES SHALL NOT EXCEED 1.5% IN ANY DIRECTION.

3. ALL ACCESSIBLE ROUTES SHALL COMPLY WITH CURRENT ADA ACCESSIBILITY GUIDELINES FOR BUILDING AND FACILITIES (ADAAG).

 BLDG THRESHOLD TRANSITION: TOP OF CONCRETE OUTSIDE DOOR = FF ELEV. MINUS 0.02'. SLOPE CONCRETE 1.5% AWAY FROM BLDG.

GRADING LABEL LEGEND

<u>CALLOUT</u> <u>DESCRIPTION</u>

X.X% GRADING SLOPE AND DIRECTION (DOWNHILL)

SPOT ELEVATION DESCRIPTION LISTED BELOW. NO DESCRIPTION MEANS TP XX.XX XX BOW BACK OF WALK **BOTTOM OF STEP BOTTOM OF WALL EXISTING GRADE** FINISHED FLOOR FLOW LINE GUTTER HIGH POINT LOW POINT RIM OF STRUCTURE TOP OF CURB TOP OF GROUND


TOP OF PAVEMENT


TOP OF STEP


TOP WALL

SHEET LEGEND

~	DRAINAGE FLOW DIRECTION
	GRADE BREAK
	EX. CONTOUR MINOR
	EX. CONTOUR MAJOR
4 9	CONTOUR MINOR (FG)
50	CONTOUR MAJOR (FG)







Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS




PK21052

Issue: 06.21.2023
heck By: BLU/EME

PROPOSED PHASE 2 GRADING PLAN

C3.1
DESIGN REVIEW

Plotted: 10/4/23 at 1:57pm By: eeykelbosch



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



PK21052


Issue: 06.21.2023
heck By: BLU/EME

Baysinger Partners Architecture

PROPOSED
PHASE 2
GRADING
ENLARGEMENT


C3.2
DESIGN REVIEW

Plotted: 10/4/23 at 1:57pm By: eeykelbosch



WASHINGTON COUNTY RIGHT OF WAY

THE PROJECT IS ASSOCIATED WITH WASHINGTON COUNTY PERMIT NUMBER 222449





Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS

Revisions

PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

PROPOSED
PHASE 2
GRADING
ENLARGEMENT
- ADA RAMP
C3.3
DESIGN REVIEW

(x) KEY NOTES

- 1 COORDINATE WATER SERVICE POINT OF CONNECTION TO EXISTING 8" MAIN WITH TVWD.
- 2 FIELD VERIFY LOCATION AND IE OF EXISTING 8" PRIVATE SANITARY SEWER. CONNECT PROPOSED LATERAL TO PRIVATE SEWER MAIN WITH PVC GASKETED SADDLE.
- 3 FIELD VERIFY LOCATION AND IE OF EXISTING 12" STORM SEWER. CONNECT PROPOSED LATERAL TO MAIN WITH TEE PER DETAIL 1/C5.1.
- 4 NOT USED
- 5 FIELD VERIFY LOCATION AND IE OF EXISTING 12" STORM SEWER. CONNECT PROPOSED LATERAL TO MAIN WITH COTG.
- 6 CONTRACTOR TO COORDINATE WITH PGE FOR THE INSTALLATION OF THE TRANSFORMER. RELOCATE ADJACENT UTILITIES AS NECESSARY.
- 7 CONTRACTOR TO COORDINATE WITH PGE FOR THE INSTALLATION OF THE TRANSFER VAULT.

SHEET LEGEND

- DOUBLE CHECK DETECTOR VAULT DOUBLE CHECK VALVE ASSEMBLY
- CONNECT TO WASTE LINE. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- CONNECT TO STORM DRAIN. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AND IE AS NOTED.
- CONNECT TO COLD WATER SYSTEM. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- UTILITY CROSSING. PROVIDE 12" MIN. CLEARANCE, U.N.O.
 - CONNECT TO ROOF DRAIN. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AND IE AS NOTED.
- CONNECT TO BUILDING FIRE PROTECTION SYSTEM. COORDINATE WITH FIRE SPRINKLER DEFERRED SUBMITTAL.
- CONNECT TO WALL FOUNDATION DRAIN. SEE STRUCTURAL PLANS FOR CONTINUATION. SIZE AS NOTED.

SHEET NOTES

- 1. PIPE BEDDING AND BACKFILL FOR ALL UTILITIES SHALL BE DONE PER DETAIL 1/C5.2.
- 2. STRUCTURES LOCATIONS ARE BASED ON CENTER OF STRUCTURE.
- 3. CONTRACTOR TO VERIFY TIE-IN ELEVATION AND COMMUNICATE ANY DISCREPANCIES TO THE ENGINEER OF RECORD.
- 4. REFERENCE SHEET C4.2 FOR UTILITY STRUCTURE TABLE
- 5. REFERENCE SHEET C4.3 FOR FIRE PROTECTION PLAN
- 6. 2" VENTING PIPE SHALL BE PROVIDED BETWEEN GREASE INTERCEPTOR VAULT AND BUILDING. COORDINATE VENTING AS REQUIRED PER OREGON PLUMBING CODE.

UTILITY LABEL LEGEND

PIPE LABEL —— UTILITY LENGTH ----- UTILITY SIZE — UTILITY TYPE XXLF - XX" XX

S=X.XX%

— SLOPE (WHERE APPLICABLE)


STRUCTURE TYPE

<u>(</u>	CALLOUT	DESCRIPTION	DETAIL REF.
,	AB AD BEND	ACCESS BASIN ————————————————————————————————————	9 C5.2 C5.2
-	CB	TRAPPED CATCH BASIN ———	C5 2
	COTG CONN	CLEANOUT TO GRADE ————————————————————————————————————	C5.2
	FCMH	FLOW CONTROL MANHOLE ———	360 C5.5
•	FDC FH	FIRE DEPARTMENT CONNECTION FIRE HYDRANT —————	8 C5.5 C5.1 502
(GV	GATE VALVE	(5.6)
	LP MH	LIGHT POLE, PER LIGHTING PLAN MANHOLE	_
(OUTFALL	OUTFALL	(3) (5.2) (2)
	OVERFLOW STUB	OVERFLOW INLET CS	5.5 (5.5)
	TD	TRENCH DRAIN —	(5) (C5.2)
	TEE WYE	TEE CONNECTION WYE CONNECTION	
(··· –	STRATA 1500 GREASE INTERCEPT 75 GPM GREASE INTERCEPTOR — WATER METER BACKWATER VALVE	76 NC



Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600

mattl@BaysingerPartners.com







PETERKORT TOWNE SQUARE STARBUCKS

PK21052 Drawn/Check By:

PROPOSED PHASE 2 UTILITY PLAN

DESIGN REVIEW





SHEET NOTES


- 1. PIPE BEDDING AND BACKFILL FOR ALL UTILITIES SHALL BE DONE PER DETAIL 1/C5.2.
- 2. STRUCTURES LOCATIONS ARE BASED ON CENTER OF STRUCTURE.
- 3. CONTRACTOR TO VERIFY TIE-IN ELEVATION AND COMMUNICATE ANY DISCREPANCIES TO THE ENGINEER OF RECORD.
- 4. REFERENCE SHEET C4.2 FOR UTILITY STRUCTURE TABLE
- 2" VENTING PIPE SHALL BE PROVIDED BETWEEN GREASE INTERCEPTOR VAULT AND BUILDING. COORDINATE VENTING AS REQUIRED PER OREGON PLUMBING CODE.

(X) KEY NOTES

- 1 TVWD TO INSTALL 2" SERVICE AND 1.5" WATER METER
- 2 REFERENCE SHEET C4.3 FOR FIRE LINE HOT TAP INSTRUCTIONS
- 3 CONTRACTOR TO INSTALL BACKFLOW PER TVWD DETAIL 605
- 4 REFERENCE SHEET C4.3 FOR FIRE PROTECTION PLAN
- 5 CONTRACTOR TO COORDINATE WITH TVWD FOR FH CONNECTION

UTILITY LABEL LEGEND

PIPE LABEL



S=X.XX%

SLOPE (WHERE APPLICABLE)


STRUCTURE TYPE

CALLOUT	DESCRIPTION	<u>DETAIL REF.</u>
AB AD BEND CB COTG CONN FCMH FDC FH	ACCESS BASIN — AREA DRAIN — BEND, USE FITTING IF APPLICABLE TRAPPED CATCH BASIN — CLEANOUT TO GRADE— CONNECTION FLOW CONTROL MANHOLE — FIRE DEPARTMENT CONNECTION FIRE HYDRANT —	(4) (5.2) (2) (5.2) (360) (8) (5.5)
GV MH OUTFALL OVERFLOW STUB TD TEE WYE	GATE VALVE MANHOLE OUTFALL OVERFLOW INLET STUB TRENCH DRAIN TEE CONNECTION WYE CONNECTION	3 C5.2 C5.5 C5.5 C5.2

SHEET LEGEND

GI GB-75

DCD DOUBLE CHECK DETECTOR VAULT





GI STRATA-1500 STRATA 1500 GREASE INTERCEPTOR

WATER METER

75 GPM GREASE INTERCEPTOR

- S CONNECT TO WASTE LINE. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- CONNECT TO STORM DRAIN. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AND IE AS NOTED.
- W CONNECT TO COLD WATER SYSTEM. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- UTILITY CROSSING. PROVIDE 12" MIN. CLEARANCE, U.N.O.
- CONNECT TO ROOF DRAIN. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AND IE AS NOTED.
- CONNECT TO BUILDING FIRE PROTECTION SYSTEM.
 COORDINATE WITH FIRE SPRINKLER DEFERRED SUBMITTAL.





Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600







PETERKORT TOWNE SQUARE STARBUCKS





Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

© 2022 Baysinger Partners Architecture

PROPOSED
PHASE 2
UTILITY
ENLARGEMENTS

C4.1
DESIGN REVIEW

NORTHING EASTING RIM ELEVATION INVERT ELEVATIONS

681863.05 7615379.04

IE 8"(IN) = 306.52 (S)

IE 4"(IN) = 306.69 (E)

IE 8"(OUT) = 306.52 (N)

IE 4"(OUT) = 308.50 (SW)

STRUCTURE ID

CONN-1

KEYNOTE

35


SS STUB-4

681947.91 7615368.64

SD STRUCTURE TABLE (XX)

KEYNOTE	STRUCTURE ID	NORTHING	EASTING	RIM ELEVATION	INVERT ELEVATIONS
1	CONN-1	681793.94	7615410.09		IE 8"(IN) = 300.17 (NW)
2	COTG-1	681838.04	7615385.48		IE 8"(IN) = 304.21 (SW) IE 6"(IN) = 304.21 (NW) IE 8"(OUT) = 304.21 (SE)
3	FCMH-1	681833.72	7615377.59	309.56	IE 8"(IN) = 304.39 (SW) IE 8"(OUT) = 304.39 (NE)
4	OVERFLOW-1	681819.07	7615350.84	309.64	IE 4"(IN) = 307.60 (SE) IE 12"(IN) = 304.99 (NW) IE 6"(IN) = 304.39 (W) IE 8"(OUT) = 304.39 (NE)
5	OVERFLOW-2	681882.36	7615316.17	309.64	IE 4"(IN) = 307.60 (NW) IE 12"(OUT) = 304.99 (SE
6	CB-1	681820.44	7615403.11	308.73	IE 6"(OUT) = 306.23 (SW)
7	CB-2	681862.15	7615367.72	309.60	IE 6"(OUT) = 307.10 (NE)
8	COTG-2	681876.90	7615364.20		IE 6"(IN) = 305.13 (NE) IE 6"(IN) = 305.13 (NW) IE 6"(OUT) = 305.13 (SE)
10	COTG-3	681895.16	7615397.53		IE 4"(IN) = 306.73 (NE) IE 6"(IN) = 308.14 (SE) IE 6"(IN) = 308.14 (NW) IE 6"(OUT) = 306.73 (SW)
11	STUB-1	681887.80	7615401.56		IE 6"(OUT) = 308.50 (NW)
12	TD-1	681898.47	7615398.55	311.42	IE 4"(OUT) = 309.38 (SW)
13	BEND-1	681903.49	7615392.97		IE 4"(IN) = 308.33 (N) IE 4"(IN) = 308.33 (NW) IE 6"(OUT) = 308.33 (SE)
14	STUB-2	681911.50	7615395.31		IE 4"(OUT) = 308.50 (S)
15	AD-1	681914.26	7615429.28	311.06	IE 4"(IN) = 308.56 (NE) IE 4"(OUT) = 308.32 (SW)
16	AD-2	681921.82	7615443.09	311.39	IE 4"(OUT) = 309.38 (SW)
17	COTG-5	681937.20	7615331.18		IE 6"(IN) = 307.78 (SW) IE 6"(OUT) = 307.78 (SE)
18	CB-3	681935.27	7615327.67	310.36	IE 6"(OUT) = 307.86 (NE)
19	STUB-3	681949.66	7615367.68		IE 6"(OUT) = 308.50 (SW)
20	NODE-2	681920.56	7615375.07		IE 4"(IN) = 308.35 (NE) IE 4"(OUT) = 308.35 (SE)

KEYNOTE	STRUCTURE ID	NORTHING	EASTING	RIM ELEVATION	INVERT ELEVATIONS
30	EXMH-1	682157.72	7615282.87	310.94	IE 10"(IN) = 303.98 (SE) IE 24"(IN) = 303.86 (W) IE 24"(OUT) = 303.54 (N)
31	FCMH-2	682141.64	7615294.77	310.99	IE 6"(IN) = 304.13 (E) IE 12"(IN) = 304.73 (SE) IE 10"(OUT) = 304.13 (NV
32	AB-1	682127.01	7615286.54	311.02	IE 10"(IN) = 306.24 (NW) IE 24"(OUT) = 304.64 (SE IE 12"(OUT) = 305.67 (SV
33	COTG-6	682132.16	7615283.72		IE 10"(IN) = 306.36 (W) IE 10"(OUT) = 306.36 (SE
34	COTG-7	682131.20	7615262.58		IE 10"(IN) = 306.78 (SW) IE 10"(OUT) = 306.78 (E)
35	COTG-8	682087.31	7615182.44		IE 12"(IN) = 308.61 (SE) IE 10"(OUT) = 308.61 (NE
36	CB-4	682113.99	7615248.99	311.78	IE 6"(OUT) = 309.28 (NW
40	OVERFLOW-3	682057.56	7615324.57	309.13	
41	OVERFLOW-4	682095.02	7615304.06	309.13	
42	OUTFALL-1	682045.46	7615326.89		IE 6"(IN) = 309.22 (S)
43	CB-5	681992.19	7615309.04	311.05	IE 6"(OUT) = 309.50 (N)
44	OUTFALL-2	682050.31	7615335.22		IE 6"(IN) = 309.24 (E)
45	STUB-4	682031.10	7615368.78		IE 4"(OUT) = 309.52 (NW
46	OUTFALL-3	682058.18	7615317.65		IE 6"(IN) = 309.40 (SW)
47	CB-6	682049.97	7615302.66	311.01	IE 6"(OUT) = 309.51 (NE)
48	OUTFALL-4	682108.41	7615296.87		IE 6"(IN) = 309.31 (N)
49	CB-7	682150.86	7615280.71	311.03	IE 6"(OUT) = 309.54 (S)
50	STUB-5	681910.60	7615389.07		IE 4"(OUT) = 308.50 (SE)
51	STUB-6	682027.15	7615376.04		IE 6"(OUT) = 309.50 (NE)
52	STUB-7	681964.79	7615357.21		IE 4"(OUT) = 308.77 (SE)
53	STUB-8	682005.48	7615336.84		IE 4"(OUT) = 310.00 (SW
54	OUTFALL-5	681798.74	7615362.02		IE 4"(IN) = 306.95 (SE)
55	BWV-1	681856.82	7615470.80		



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



A Revisions

Original Issue:
Drawn/Check By:

OKA 21.052

06.21.2023
BLU/EME

Drawn/Check By: BLU/EME

© 2022 Baysinger Partners Architecture

PROPOSED
PHASE 2 UTILITY
STRUCTURE
TABLE

C4.2
DESIGN REVIEW

W STRUCTURE TABLE 🗱


KEYNOTE	STRUCTURE ID	NORTHING	EASTING	
1	STUB-1	681863.21	7615412.18	
2	2 STUB-2		7615384.65	
3	STUB-3	681958.16	7615359.60	

SHEET NOTES

- 1. PIPE BEDDING AND BACKFILL FOR ALL UTILITIES SHALL BE DONE PER DETAIL 1/C5.2.
- 2. STRUCTURES LOCATIONS ARE BASED ON CENTER OF STRUCTURE.
- 3. CONTRACTOR TO VERIFY TIE-IN ELEVATION AND COMMUNICATE ANY DISCREPANCIES TO THE ENGINEER OF RECORD.

FP STRUCTURE TABLE 🕸

KEYNOTE	STRUCTURE ID	NORTHING	EASTING
1	STUB-1	681860.58	7615413.62
2	STUB-2	681960.79	7615358.16



× KEY NOTES

- 1 COORDINATE WATER SERVICE POINT OF CONNECTION TO EXISTING 8" MAIN WITH TVWD.
- 2 CONTRACTOR TO HOT TAP EXISTING WATERLINE WITH 8"X4"
 TAPPING SADDLE AND 4" FLGXMJ GATE VALVE PER TVWD DETAIL
 302
- 3 CONTRACTOR TO INSTALL 4" DCDA PER TVWD DETAIL 801

SHEET LEGEND

- DCD DOUBLE CHECK DETECTOR VAULT (80°)
- CONNECT TO BUILDING FIRE PROTECTION SYSTEM.
 COORDINATE WITH FIRE SPRINKLER DEFERRED SUBMITTAL.
- FIRE DEPARTMENT CONNECTION

 8

 C5.1

UTILITY LABEL LEGEND

PIPE LABEL

UTILITY LENGTH

UTILITY SIZE

UTILITY TYPE

XXLF - XX" XX

S=X.XX%


STRUCTURE TYPE

CALLOUT DESCRIPTION DETAIL REF.

BEND BEND, USE FITTING IF APPLICABLE


— SLOPE (WHERE APPLICABLE)

BEND BEND, USE FITTING IF APPLICABLE
FDC FIRE DEPARTMENT CONNECTION 8
C5.1
GV GATE VALVE
STUB




WATER ENLARGEMENT-1

SCALE: 1" = 5'



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS


Revision


PK21052
ginal Issue: 06.21.2023
wn/Check By: BLU/EME


PROPOSED
PHASE 2 FIRE
PROTECTION


PLAN

C4.3
DESIGN REVIEW










NOTES:

1. CONSTRUCT CONTRACTION JOINTS AT 15' MAX. SPACING AND AT RAMPS. CONSTRUCT EXPANSION JOINTS AT 200' MAX SPACING, AT POINTS OF TANGENCY AND AT ENDS OF EACH DRIVEWAY, UNLESS NOTED OTHERWISE.

8 CONCRETE SIDEWALK
SCALE: NTS



CONCRETE CURB ENDING

AC COURSE:
2.5" OF 1/2" DENSE GRADED,
LEVEL 2 HMAC

COMPACTED
SUBGRADE
COURSE


COURSE

COMPACTED
SUBGRADE
COURSE

COURSE

COURSE

ASPHALT PAVEMENT SECTION




CONSTRUCT CONTRACTION JOINTS AT 15' MAX. SPACING AND AT RAMPS.
 CONSTRUCT EXPANSION JOINTS AT 200' MAX. SPACING AT POINTS OF TANGENCY AND AT ENDS OF EACH DRIVEWAY.

2. PROVIDE MEDIUM TO COARSE BROOM FINISH.

HEAVY CONCRETE PAVEMENT SECTION

SCALE: NTS




NOTES:

1. CURB EXPOSURE 'E' = 6", TYP. VARY AS SHOWN ON PLANS OR AS DIRECTED.

- 2. CONSTRUCT CONTRACTION JOINTS AT 15' MAX. SPACING AND AT RAMPS. CONSTRUCT EXPANSION JOINTS AT 200' MAX SPACING AT POINTS OF TANGENCY AND AT ENDS OF EACH DRIVEWAY
- 3. TOPS OF ALL CURBS SHALL SLOPE TOWARD THE ROADWAY AT 2% UNLESS OTHERWISE SHOWN OR AS DIRECTED.
- 4. DIMENSIONS ARE NOMINAL AND MAY VARY TO CONFORM WITH CURB MACHINE AS APPROVED BY THE ENGINEER.

4 STANDARD CONCRETE CURB



NOTES:

1. DIMENSIONS ARE NOMINAL AND MAY VARY TO CONFORM TO MANUFACTURER'S PRODUCTS APPROVED BY ENGINEER.

PRECAST CONCRETE WHEEL STOP

SCALE: NTS

Payeinger

Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com



FROELICH
ENGINEERS
DIVIL STRUCTURAL
Portland, OR. | Bend, OR. | Denver, CO. (503) 624-7005

PETERKORT TOWNE SQUARE STARBUCKS

A Revisions

PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME
©2022 Baysinger Partners Architecture

PROPOSED
PHASE 2
TYPICAL
DETAILS

C5.0
DESIGN REVIEW

MIN. 3000 PSI CONCRETE ANCHOR PAD TO BE 12"x12"x6" THICK, UNLESS NOTED OTHERWISE. ELIMINATE IF INSTALLED IN CONCRETE PAVED AREA.

- 2. USE FLANGE OR THREADED FITTINGS.
- CONTRACTOR SHALL PROVIDE SINGLE CHECK VALVE AND BALL DRIP VALVE IN ACCESSIBLE LOCATION INSIDE DCDA VAULT. COORDINATE WITH PLUMBING.
- 4. REFER TO DETAIL 3/C5.1 FOR BOLLARD LOCATIONS AROUND FDC

FIRE DEPARTMENT CONNECTION (FDC) DUAL PORT SCALE: NTS

3'-6" 1'-9½" - 2'-2¾" -

PLAN VIEW

SIDE VIEW

GREASE INTERCEPTOR

- Corrosion resistant cooling/liner available to extend the line of the tank.

Manufacture's recommendations:

- Fill lift anchor pockets with grout.

- Ventilate each end to open atmosphere.

- Prior to "Start Up" of System, fill with clean water through inlet bay to bottom of flow channel (approx. one foot deep).

- Follow Regular Inspection, Cleaning, & Maintenance Schedule (See Clean Out & Maintenance Instructions).

30" Grade Rings Available (Recommended 12" Maximum)

- Butyl Resin Sealant

Risers Available

Hook Lift Anchor (4 Places in Top & Bose)


for 4" & 6" Pipe

STRATA

GREASE INTERCEPTOR


GGI-1500 GALLON

- INSTALL (2) 2-WAY MAINTENANCE CLEANOUTS 24" UPSTREAM AND DOWNSTREAM OF UNIT.
- INSTALL VENT TO HYDROMECHANICAL GREASE INTERCEPTOR AS REQUIRED BY THE OREGON SPECIALITY PLUMBING CODE.
- USE NO. 4 REBAR GRADE 60 STEEL PER ASTM A615: CONNECTED WITH TIE WIRE. REBAR TO BE 2.5" FROM EDGE OF CONCRETE AND SPACED IN A 12" GRID WITH 4" SPACING AROUND ACCESS OPENINGS.



TP=TOP OF PAVEMENT

- TW=TOP OF WALL




NOTES:

1. PVC TO PVC COUPLER

STANDARD GRAVITY TEE CONNECTION SCALE: NTS

CUSTOMER SIDE METER SIDE

<u>PLAN</u>




INSTALLATION SHOWN IS ONLY A SUGGESTION. THE DISTANCE FROM BOTTOM OF DEVICE TO FINISH GRADE, FREEZE PROTECTION, AND CLEARANCE FOR TESTING & REPAIR ARE THE MAJOR CONSIDERATIONS FOR INSTALLATION. PLUGS TO BE INSTALLED IN TEST COCKS OF BELOW GROUND INSTALLATIONS (NO DISSIMILAR METALS). IF FREEZE PROTECTION IS PROVIDED, THE

24" MIN CLEARANCE MAY BE REDUCED.

DOUBLE CHECK BACKFLOW ASSEMBLY

FACE OF CURB OR -EDGE OF PAVEMENT

BOLLARD - PLAN VIEW



PLANTER CURB SCALE: NTS

schierproducts.com

SCHIER STANDARD INSTALLATION

NOTES:

1. INSTALL PER OLDCASTLE INSTALLATION REQUIREMENTS STRATA 1500 GREASE INTERCEPTOR

Tel: (503) 682-2844 Fax: (503) 682-2657 oldcastleprecast.com/wilsonvi

STRATA GREASE INTERCEPTOR - 1500

INLET

w/Flexible Boot
Connector
for 4" & 6" Pipe

H

Grease Interceptor:

Designed in accordance with IAPMO/ANSI Z1001, Manufactured per ASTM C1613

Loading per ASTM C890 for AASHTO HS20-44 vehicle loading and maximum soil cover of 5'-0"

Maximum allowable DFUs (Drainage Fixture Units) = 172 (equivalent to 1,500 gallon size)

Corrosion resistant coating/liner available to extend the life of the tank.

Oldcastle Precast®

SCALE: NTS

PO Box 323, Wilsonville, Oregon 97070-0323 Issue Date: 2016

SPECIFICATIONS 1. 4" FPT inlet/outlet with 4" plain end adapters, single inlet and triple outlet. add 1,043 lbs.) Maximum operating temperature: 150° F continuous Capacities - Liquid: 125 gal. Grease: 861 lbs. (118 gal.) @75 GPM Solids: 31 gal. 5. For gravity drainage applications only. 6. Do not use for pressure applications. . Cover placement allows full access to tank for proper maintenance. 8. Vent not required unless per local code. Outlet B 9. Engineered inlet and outlet diffusers with inspection ports are removable to inspect / clean piping. 10. Integral air relief / Anti-siphon / Sampling access. 11. Adjustable cover adapter provides up to 4" of additional 12. Designed for below-grade, above-grade, indoor and outdoor installations. 13. Safety Star®, access restrictor built into cover adapter, prevents accidental entry to tank TOP VIEW
(COVER REMOVED FOR CLARITY) (Optional) Adjustable Adapter with — H-20 rated cast iron cover ISOMETRIC VIEW ENGINEER SPECIFICATION GUIDE Ø 24-1/2" TYP ───- Schier Great Basin™ grease interceptor model # GB-75 shall be lifetime guaranteed and made in USA of seamless, rotationallymolded polyethylene with minimum 3/8" uniform wall thickness. Interceptor shall be furnished for above or below-grade installation with adjustable cover adapter, Safety Star® access restrictor built into each cover adapter, and three outlet options. 4" Outlet Interceptor shall be certified to ASME A112.14.3 (Type D) and CSA B481.1. Interceptor flow rate shall be 75 GPM. Interceptor grease capacity shall be 861 lbs. Cover shall provide water/gas-tight seal and have minimum 16,000 lbs. load Static Water Line CERTIFIED PERFORMANCE Great Basin™ hydromechanical grease interceptors are third party performance-tested and listed by IAPMO to ASME #A112.14.3 and CSA B481.1 grease interceptor standards and greatly exceed requirements for grease separation and storage. 24-3/8" INVERT They are compliant to the Uniform Plumbing Code and the International Plumbing Code. SECTION A-A END VIEW Type D certification does not require a flow control **SPECIFICATION SHEET** SCHIER **MODEL NUMBER: PART NUMBER:** 4045-007-02 **GB-75** 6455 Woodland Dr Shawnee, KS 66218 Tel: 913-951-3300 GB-75 GREASE INTERCEPTOR 75 GPM, 4" INLET/OUTLET, H-20 RATED CAST IRON COVER PROPRIETARY AND CONFIDENTIAL Fax: 913-951-3399

1. INSTALL PER SCHIER STANDARD INSTALLATION DETAIL 7/C5.1

DWG BY: C. BUSENITZ DATE: 4/14/2022 REV: -

GB-75 GREASE INTERCEPTOR SCALE: NTS

Plotted: 10/4/23 at 1:58pm By: eeykelbosch

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com

Baysinger

Well-crafted simplicity. Portland, OR. | Bend, OR. | Denver, CO

PETERKORT TOWNE SQUARE STARBUCKS

A Revisions

PK21052 Original Issue: 06.21.2023

BLU/EME

©2022 Baysinger Partners Architecture **PROPOSED** PHASE 2 **TYPICAL**


DETAILS

Drawn/Check By:

DESIGN REVIEW

10 PLUG


SCALE: NTS



NOTE:

1. NYLOPLAST 12" DRAIN BASIN WITH 6" SUMP AND LIGHT DUTY GRATE AND FRAME OR APPROVED EQUAL.

11) AREA DRAIN
SCALE: NTS




NOTES:


1. CONSTRUCT GUTTER ADJACENT TO PROPOSED CURB. CONSTRUCT MONOLITHICALLY OR SEDARATE

12) CONCRETE GUTTER

SCALE: NTS



13 HEAVY ASPHALT PAVEMENT SECTION SCALE: NTS




NOTES:


1. EXTENDABLE BACKWATER VALVE TO BE MANUFACTURED BY CLEAN CHECK OR
APPROVED EQUAL AND SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.

14 EXTENDABLE BACKWATER VALVE

SCALE: NTS



7 DOWNSPOUT/STORM DRAIN CONNECTION
SCALE: NTS




NOTES:

1. NYLOPLAST CLEANOUT END CAP OR APPROVED EQUAL. ADJUST TO FINISHED GRADE

2 PERFORATED PIPE TO MEET ODOT SPECIFICATION 02415.50. LOCATE AT BOTTOM OF STORAGE SECTION WITH HOLES ON TOP HALF OF PIPE.


8 PLANTER CLEANOUT AND PERF PIPE
SCALE: NTS



NOTE:

1. BASIN STRUCTURE SHALL BE NYLOPLAST OR APPROVED EQUAL

9 ACCESS BASIN
SCALE: NTS



NOTES:

1. CONTRACTOR TO WIDEN EXCAVATION AS REQUIRED TO OBTAIN COMPACTION WITH CONTRACTORS COMPACTION EQUIPMENT.

TRAPPED CATCH BASIN

2. 1/4" STEEL PLATE, BITUMINOUS COATED. AS MANUFACTURED BY GIBSON STEEL BASINS OR APPROVED EQUAL.

SEE NOTE 2

PAVERS, PER LANDSCAPE PLAN

LANDSCAPE PLAN

SEE NOTE 2

PAVERS, PER LANDSCAPE PLAN

SEE NOTE 2

PAVERS, PER LANDSCAPE PLAN

NOTES:

1. TRENCH DRAIN SHALL BE NEUTRAL-SLOPED 4" WIDE ZURN OR ACO TRENCH DRAIN OR APPROVED EQUAL.


SECTION

2. TRENCH DRAINS GRATE SHALL BE LOCKABLE HEAVY DUTY TRENCH GRATE - CLASS C.

3. TRENCH SYSTEM SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS.

TRENCH DRAIN - 4 INCH WIDE


SEE NOTE 1




NOTES:

1. STRUCTURAL DESIGN OF WALL, FOUNDATION, FABRIC AND BACKFILL MATERIAL PER
STRUCTURAL PLANS





1 TYPICAL PIPE BEDDING AND BACKFILL
SCALE: NTS




2. FOR CARRIER PIPE SIZE 6" \varnothing AND LESS, PROVIDE RISER PIPE SIZE TO MATCH CARRIER PIPE.

3. FOR CARRIER PIPE SIZE 8" \varnothing AND LARGER, RISER PIPE SHALL BE 6" \varnothing .

4. RISER PIPE MATERIAL TO MATCH CARRIER PIPE MATERIAL.





3 TYPICAL OUTFALL RIP-RAP PROTECTION
SCALE: NTS



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



Original Issue:
Drawn/Check By:


© 2022 Baysinger Partners Architecture


PROPOSED
PHASE 2


TYPICAL DETAILS


C.5 2


DESIGN REVIEW











Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com






PETERKORT TOWNE SQUARE STARBUCKS





PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME
© 2022 Baysinger Partners Architecture


PROPOSED PHASE 2 TYPICAL DETAILS


C5.3
DESIGN REVIEW











Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

©2022 Baysinger Partners Architecture

PROPOSED


PHASE 2


TYPICAL DETAILS

C5.4

DESIGN REVIEW

Plotted: 10/4/23 at 1:58pm By: eeykelbosch





Low Impact Development Approaches Handbook

CleanWater Services

NYLOPLAST 30" DRAIN BASIN WITH -

DOME GRATE. SEE NOTE 3.

12" CONNECTION

8" OUTLET PIPE ·

IE=PER PLAN

2. INSTALL CHAMBERS PER PLAN AND MANUFACTURER RECOMMENDATIONS

1. INSTALL HIGH DENSITY JUTE OR COCONUT FIBER MATTING, AS APPROVED BY LANDSCAPE ARCHITECT.


PLANTINGS, SEE -

CONTECH SC-740

PER DETAILS ON

SHEET C5.4

LANDSCAPE PLANS



1. INSTALL HIGH DENSITY JUTE OR COCONUT FIBER MATTING, AS APPROVED BY LANDSCAPE ARCHITECT.

- 2. INSTALL CHAMBERS PER PLAN AND MANUFACTURER RECOMMENDATIONS
- 3. NYLOPLAST 10" INLINE DRAIN WITH DOME GRATE. RUBBERIZED COATING APPLIED TO EXPOSED PVC OUTER SURFACE BY MANUFACTURER. COATING SHALL EXTEND 12" FROM TOP OF DRAIN.

- NYLOPLAST 30" DRAIN BASIN WITH

 \TYP

PLANTER CLEANOUT

PER 8/C5.2

DOME GRATE. SEE NOTE 3.

4" PERF. PIPE

12" CONNECTION

PIPE

DRAINAGE FABRIC PER

CHAMBER MANUFACTURER

REQUIRED. SEE SHEET C5.4





Baysinger





PETERKORT TOWNE SQUARE STARBUCKS

PK21052 06.21.2023 Drawn/Check By:


©2022 Baysinger Partners Architecture **PROPOSED** PHASE 2

TYPICAL


DETAILS C5.5 **DESIGN REVIEW**

BLENDED SOIL SPECIFICATION

126







NOTES:
1. CONCRETE SHALL BE 3000 PSI.

- 2. INSTALL CONTRACTION AND EXPANSION JOINTS AT SPECIFIED DISTANCE.
- 3. BACK OF MOUNTABLE CURB TO ALIGN WITH BACK OF ADJACENT STANDARD CURB LINE.

GROWING MEDIUM, PER -CWS BLENDED SOIL


3" DEEP (3/4"-1/4")

9" DEEP DRAIN

CLEAN CRUSHED

DRAIN ROCK

3. RUBBERIZED COATING APPLIED TO EXPOSED PVC OUTER SURFACE BY MANUFACTURER. COATING SHALL EXTEND 12" FROM TOP OF DRAIN. RAIN GARDEN, TYPE 2



EAST JORDAN MODEL #3639Z1 (OR APPROVED EQUAL) VALVE BOX. EAST JORDAN MODEL #3639A1 COVER WITH "TVWD" CAST IN TOP SURFACE. VALVE BOX SHALL BE PLUMB. CENTERED ON AXIS OF OPERATING NUT. AND SHALL NOT REST ON OPERATING ASSEMBLY

UNPAVED AREAS ONLY: PROVIDE 4" THICK CONCRETE PAD OVER 4" COMPACTED 1"-0" CRUSHED ROCK. PAD SHALL EXTEND OF A MINIMUM OF 6" AROUND VALVE BOXES. REINFORCE CONCRETE WITH #4 REBAR MAX 12" O.C. CENTERED VERTICALLY IN SLAB. PROVIDE 3" CLEARANCE FROM EDGES AND PENETRATIONS.

6" TYPE SDR 35 PVC, D3034 PIPE SPACER. LENGTH AS NECESSARY. OPERATOR EXTENSION REQUIRED WHEN VALVE NUT IS 60" OR DEEPER FROM FINISHED

GRADE, SEE DETAIL 403. WRAP VALVE WITH POLYETHYLENE ENCASEMENT, OR APPROVED EQUAL PRIOR TO BACKFILLING. EXTEND POLYETHYLENE 6" MINIMUM BEYOND VALVE AND SECURE TO PIPE WITH 10 MIL PVC TAPE. SEE DETAIL 301.

VALVES 8" AND SMALLER SHALL BE MJ GATE VALVES. VALVES 12" AND LARGER SHALL BE MJ BUTTERFLY VALVES. 2" SQUARE OPERATING NUT.

H. 8" X 6" PVC SDR35 REDUCER SXS, CONNECT TO D3034 PIPE USING A COMPATIBLE PVC CEMENT

COMPACTED ROCK.

DETAIL

SUMP DETAILS.

DATE: 9/2020

DETAIL

A. ONLY ELECTRIC SUMP PUMPS ALLOWED IN BACKFLOW VAULTS

1. REFER TO OAR FOR ALL CLEARANCES AND TO OHA FOR LIST

MINIMUM AROUND BASE OF VAULT WHERE FLOODING OR HIGH

2. CONTRACTOR TO SEAL ALL OPENINGS IN VAULT WITH NON

3. CONTRACTOR TO INSTALL CONCRETE BALLAST 3 CU YDS

-. THRUST BLOCK 1'-0" MINIMUM THICKNESS

DOUBLE CHECK VALVE

ASSEMBLY

OR DOUBLE CHECK

DETECTOR ASSEMBLY


OF APPROVED ASSEMBLIES

5. FOR USE ON FIRE SERVICE LINE


GROUND WATER EXISTS


SHRINK GROUT

DATE: 11/2019 DESIGNED: MBA **DETAIL TUALATIN VALLEY** TYPICAL VALVE SETTING APPROVED: NWA SCALE: NONE



- . CUT THE POLYETHYLENE TUBE TWO FEET LONGER THAN PIPE AND SLIP OVER PIPE AS
- 2. SPREAD THE POLYETHYLENE TUBE AS SHOWN SO THAT ENOUGH IS LEFT TO PROVIDE A ONE FOOT OVERLAP AT EACH END OF PIPE.
 - TAKE UP SLACK IN THE TUBE ALONG THE PIPE BARREL, MAKING A SNUG BUT NOT TIGHT FIT. FOLD OVER ON TOP OF PIPE AND SECURE IN PLACE WITH ONE LAYER OF CIRCUMFERENTIALLY OR SPIRAL WRAPPED TAPE ABOUT TWO FEET ON CENTER. (PE SHOWN LOOSE FOR CLARITY) TAPE SHALL BE 10-MIL BLACK ADHESIVE PVC TAPE, CHRISTY'S PIPE WRAP TAPE, OR APPROVED EQUAL.
- 4. LOWER PIPE INTO TRENCH, BEING SURE THAT THE POLYWRAP IS NOT DAMAGED, AND MAKE UP JOINT.
- . PULL POLYETHYLENE FORWARD FROM PREVIOUS JOINT OVER THE BELL AND SECURE IN PLACE AS SHOWN.
- PULL POLYETHYLENE FROM NEW PIPE OVER THIS SAME BELL, PROVIDING A DOUBLE LAYER OF POLYETHYLENE AND SECURE IN PLACE AS SHOWN.





- . 6" GATE VALVE. WRAP TEE, VALVE, AND PIPE TO THE FOOT VALVE WITH 3 LAYERS OF POLYETHYLENE ENCASEMENT PRIOR TO BACKFILLING. EXTEND PE WRAP A MINIMUM OF 6" BEYOND TEE. SECURE TO PIPE WITH 10 MIL PVC PIPE WRAP TAPE. SEE DETAIL 301. DO NOT WRAP HYDRANT BARREL.
- TEE. NEW CONSTRUCTION TEE SHALL BE MJ X MJ X FLG. CONNECTIONS TO EXISTING MAINS SHALL BE TAPPING TEE PER DETAIL 302. THRUST BLOCK REQUIRED ONLY FOR TAPPING TEE.

MECHANICAL JOINT WITH GRIP FOLLOWER. ALL

JOINTS IN HYDRANT ASSEMBLY SHALL BE FULLY

. 12" X 12" X 8" CONCRETE PIER BLOCK ON

UNDISTURBED NATIVE SOIL.

1-1/2" CLEAN DRAIN ROCK POCKET. 4 CUBIC FEET MINIMUM. MINIMUM 6" ABOVE HYDRANT DRAIN OPENING. WRAP WITH GEOTEXTILE FABRIC PER TVWD STANDARDS.

DIRECTIONS PER DETAIL 503. PLACEMENT OF CONCRETE AROUND HYDRANTS IS PROHIBITED.


I. NO RISER KITS ON NEW HYDRANT INSTALLATIONS. J. CONCRETE BLOCK - 3500 PSI 2" BELOW SCORE LINE, 8" THICK, AND 12" BELOW BURY LINE. CONCRETE SHALL NOT IMPACT WEEP HOLE.


H. FOLLOW MANUFACTURER RECOMMENDATIONS FOR


BURY LINE AND BREAK FLANGE MAX AND MIN.

K. WRAP HYDRANT BARREL WITH PE WRAP BENEATH BURY LINE TO 6 INCHES BELOW CONCRETE BLOCK. ENSURE PE WRAP DOES NOT INTERFERE WITH WEEP HOLE.

DATE: 9/2020 DESIGNED: MBA TUALATIN VALLEY
WATER DISTRICT FIRE HYDRANT STANDARD DETAIL APPROVED: NWA INSTALLATION 502 SCALE: NONE








2. IF PROPERTY CORNER MONUMENTS HAVE NOT BEEN SET AT THE TIME OF WATER SERVICE INSTALLATION, THE DEVELOPER'S SURVEYOR SHALL SET A LATH AT THE

PROPERTY CORNER LOCATION ON THE RIGHT-OF-WAY LINE. ORS 92.044(7) PROHIBITS LOCATING ANY UTILITY INFRASTRUCTURE WITHIN 1-FT OF A SURVEY MONUMENT. DEVELOPER SHALL PAY FOR ANY RELOCATION OF SERVICES AND/OR METER BOXES FOUND TO FALL WITHIN 1—FT OF A SURVEY MONUMENT

PLACE BACKFLOW ASSEMBLY AS CLOSE TO METER AS POSSIBLE. ADHERE TO LOCAL ISOLATION REQUIREMENTS

	SULATION REQUIREMENTS.			
<u> </u>	TUALATIN VALLEY WATER DISTRICT	DESIGNED: MBA	1-1/2" & 2" METER INSTALLATION WITH	DATE: 9/2020
				DETAIL
		APPROVED: NWA	BACKFLOW PREVENTION	COF
		SCALE: NONE	DEVICE	605



SIZE SHALL BE PER TABLE 1 AND SHALL NOT BE LESS THAN ONE FOOT IN ANY DIMENSION. CONCRETE SHALL BE MINIMUM 3500 PSI. BRANCH PIPE SHALL NOT BE PRESSURIZED FOR 5 DAYS.

WRAP TAPPING SADDLE AND VALVE WITH 3 LAYERS OF POLYTHEYLENE ENCASEMENT PRIOR TO POURING THRUST BLOCK AND BACKFILLING. EXTEND POLYETHYLENE 6" MINIMUM BEYOND SADDLE AND VALVE AND SECURE TO PIPE WITH POLYETHYLENE PIPE WRAP TAPE. SEE DETAIL 301.

C. STAINLESS STEEL TAPPING SADDLE WITH GASKET AND FLANGED CONNECTION.

D. LINE—SIZE GATE VALVE (FLG X MJ) PER DETAIL 402. E. JOINTS ON BRANCH PIPE SHALL BE RESTRAINED.

BEFORE INSTALLING TAPPING SADDLE, CONTRACTOR SHALL THOROUGHLY CLEAN PIPE TO REMOVE ALL DIRT, ROCKS, AND OTHER FOREIGN MATERIAL FROM PIPE WHERE SADDLE WILL BE INSTALLED.

2. SADDLE BOLTS SHALL BE TORQUED TO MANUFACTURER'S SPECIFICATIONS. BOLTS SHALL CONFORM TO ANSI/AWWA C111/A21.11.

3. CONTRACTOR SHALL ENSURE THAT GASKET IS PROPERLY ALIGNED AND FREE OF FOREIGN MATERIAL PRIOR TO TIGHTENING SADDLE.


4. SADDLE LOCATION AND INSTALLATION SHALL BE APPROVED BY DISTRICT INSPECTOR PRIOR TO TAPPING

5. CONTRACTOR SHALL AIR TEST SADDLE TO 40 PSI PRIOR TO TAPPING.

6. CONTRACTOR SHALL FLUSH AND PRESSURE TEST VALVE FOR PRIOR TO BACKFILLING.

ENGINEER SHALL PROVIDE CALCULATION AND SIZING IF TEST PRESSURE EXCEEDS 150 PSI. SAFETY FACTOR SHALL BE 1.5.

		_ 5_ 7.5.			╙
		DESIGNED: MBA		DATE: 9/2020	П.
	TUALATIN VALLEY WATER DISTRICT	APPROVED: NWA	TAPPING SADDLE	DETAIL	
				302	į
		SCALE: NONE		002	ĮL



THE CLEAR ZONE PROHIBITS THE FOLLOWING:

- VEHICLE PARKING
- FENCES
- TREES • LARGE BUSHES
- RETAINING WALLS ANYTHING ELSE THAT MAY INTERFERE WITH OPERATION OF THE FIRE
- HYDRANT. 2. THE CLEAR ZONE ALLOWS THE FOLLOWING:
 - LAWN GRASS
 - MULCH BARK DUST
 - GROUND COVER


LOW PLANTINGS

HOWEVER. THE PROPERTY OWNERS SHOULD BE AWARE THE GROUND COVER COULD BE DAMAGED WHEN THE HYDRANT IS USED OR MAINTAINED.

3. THE CONTRACTOR SHALL INSTALL A BLUE REFLECTOR BUTTON FOR THE FIRE DEPARTMENT AFTER FINAL LIFT OF AC PAVEMENT IS PLACED.

4. WHERE ALLOWABLE WITHIN CITY OR COUNTY JURISDICTIONS, HYDRANTS MAY BE PLACED WITHIN THE SIDEWALK, IF THE SPACING REQUIREMENTS ARE MET AS SHOWN.

	DESIGNED: MBA		DATE: 9/2020
ALATIN VALLEY	ADDDOVED: NIMA	FIRE HYDRANT CLEAR	DETAIL
TER DISTRICT	APPROVED: NWA	ZONE	503
	SCALE: NONE		505



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



PK21052 06.21.2023 Original Issue: BLU/EME

Drawn/Check By: ©2022 Baysinger Partners Architecture

PROPOSED PHASE 2 **TYPICAL DETAILS**

DESIGN REVIEW

MAX DENSITY

* "OR EQUAL"

UTILITY

660-WA

577-WA

676-WA

5106-LA

TUALATIN VALLEY

WATER DISTRICT

687-WA

VAULT *

BII CO

DOOR *


J-5ALH20

JD-3ALH20


DESIGNED: MBA

APPROVED: NWA

SCALE: NONE



SITE MAP NOT TO SCALE



VICINITY MAP

BMP MATRIX: CONSTRUCTION PHASES

REFER TO DEQ GUIDANCE MANUAL FOR A COMPREHENSIVE LIST OF AVAILABLE BMP'S.

	CLEARING	SITE AND UTILITY	VERTICAL CONSTRUCTION	FINAL STABILIZATION
EROSION PREVENTION				
PRESERVE NATURAL VEGETATION	** X	Х	X	Х
GROUND COVER			Х	Х
PLASTIC SHEETING				
MATTING				
DUST CONTROL	X	X	Х	
TEMPORARY/PERMANENT SEEDING		Х	Х	Х
SEDIMENT CONTROL				
SEDIMENT FENCE (PERIMETER)	** X	Х	Х	
STRAW WATTLES		X	Х	
INLET PROTECTION	** X	X	Х	Х
RUN OFF CONTROL				
CONSTRUCTION ENTRANCE	** X	Х		
OUTLET PROTECTION				
SURFACE ROUGHENING				
CHECK DAMS				
POLLUTION PREVENTION				
PROPER SIGNAGE	Х	Х	Х	Х
HAZ WASTE MGMT	Х	Х	Х	Х
SPILL KIT ON-SITE	Х	Х	Х	Х
CONCRETE WASHOUT AREA		X		

SIGNIFIES BMP THAT WILL BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY.

APPLICANT

BAYSINGER PARTNERS CONTACT: MATTHEW LILLARD, AIA CONTACT: XXXX 2410 N. LOMBARD ST PORTLAND, OR 97217 PHONE: 503-546-1600

ENGINEERING FIRM CONTRACTOR

FROELICH ENGINEERS CONTACT: EVAN EYKELBOSCH, PE 17700 SW UPPER BOONES FERRY RD PORTLAND, OR 97XXX SUITE 115 PORTLAND, OR 97224

PHONE: XXX-XXX-XXXX PHONE: 503-624-7005

XXXXXXX

INSPECTION FREQUENCY:

	SITE CONDITION		MINIMUM FREQUENCY	
.	1.	ACTIVE PERIOD	ON INITIAL DATE THAT LAND DISTURBANCE ACTIVITIES COMMENCE. WITH 24 HOURS OF ANY STORM EVENT, INCLUDING RUNOFF FROM SNOW MELT, THAT RESULTS IN DISCHARGE TO THE SITE. AT LEAST ONCE EVERY 14 DAYS, REGARDLESS OF WHETHER STORMWATER RUNOFF IS OCCURRING.	
	2.	INACTIVE PERIODS GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDAR DAYS.	THE INSPECTOR MAY REDUCE THE FREQUENCY OF INSPECTIONS IN ANY AREA OF THE SITE WHERE THE STABILIZATION STEPS IN SECTION 2.2.20 HAVE BEEN COMPLETED TO TWICE PER MONTH FOR THE FIRST MONTH, NO LESS THAN 14 CALENDAR DAYS APART, THEN ONCE PER MONTH	
	3.	PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER.	IF SAFE, ACCESSIBLE AND PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT DISCHARGE POINT OR DOWNSTREAM LOCATION OF THE RECEIVING WATERBODY.	
	4.	PERIODS DURING WHICH CONSTRUCTION ACTIVITIES ARE SUSPENDED AND RUNOFF IS UNLIKELY DUE TO FROZEN CONDITIONS.	VISUAL MONITORING INSPECTIONS MAY BE TEMPORARILY SUSPENDED. IMMEDIATELY RESUME MONITORING UPON THAWING, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.	
	5.	PERIODS DURING WHICH CONSTRUCTION ACTIVITIES ARE SUSPENDED AND RUNOFF IS UNLIKELY DUE TO FROZEN CONDITIONS.	VISUAL MONITORING INSPECTIONS MAY BE REDUCED TO ONCE A MONTH. IMMEDIATELY RESUME MONITORING UPON THAWING, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.	

THE PERMITTEE IS REQUIRED TO MEET ALL THE CONDITIONS OF THE 1200-C PERMIT. THIS ESCP AND GENERAL CONDITIONS HAVE BEEN DEVELOPED TO FACILITATE COMPLIANCE WITH THE 1200-C PERMIT REQUIREMENTS. IN CASES OF DISCREPANCIES OR OMISSIONS. THE 1200-C PERMIT REQUIREMENTS SUPERCEDE REQUIREMENTS OF THIS PLAN.

- HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS.
- (SCHEDULE A.8.C.I.(3))
- ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS. (SCHEDULE A.12.B AND SCHEDULE B.1)
- INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS. (SCHEDULE B.1.C AND B.2)
- RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, THE ABOVE RECORDS MUST BE RETAINED BY THE PERMIT REGISTRANT BUT DO NOT NEED TO BE AT THE CONSTRUCTION SITE. (SCHEDULE B.2.C)

PROJECT LOCATION:

NEAR THE CORNER OF SW CEDAR HILLS BLVD AND SW BARNES RD. WASHINGTON COUNTY, OREGON, LATITUDE = 45.51548791888526 LONGITUDE = -122.79163875557494

PROPERTY DESCRIPTION:

TAX LOT 1S103A001600 (WASHINGTON COUNTY TAX MAP) LOCATED IN THE NORTHEAST 1/4 OF SECTION 3, TOWNSHIP 1 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN, WASHINGTON **COUNTY OREGON**

NARRATIVE DESCRIPTIONS

EXISTING SITE CONDITIONS

* DEVELOPED COMMERCIAL PROPERTY * BUILDINGS AND PARKING LOTS

DEVELOPED CONDITIONS

- * REDEVELOPMENT OF SMALL PORTION OF SITE
- * NEW BUILDINGS AND PARKING LOTS

NATURE OF CONSTRUCTION ACTIVITY AND ESTIMATED TIME TABLE

- * CLEARING (DATES, FROM & TO: MARCH 2023 MAY 2023)
- * MASS GRADING (DATES, FROM & TO: MAY 2023 JUNE 2023) * UTILITY INSTALLATION (DATES, FROM & TO: JUNE 2023 - AUG 2023)
- * SITE CONSTRUCTION (DATES, FROM & TO: JULY 2023 OCT 2023)
- * VERTICAL CONSTRUCTION (DATES, FROM & TO: JULY 2023 DEC 2023) * FINAL STABILIZATION (DATES, FROM & TO: DEC 2023 - JAN 2024)

ESTIMATE OF TOTAL PROJECT SITE AREA

TOTAL ESTIMATED SITE AREA = 716,126 SF = 16.44 ACRES

TOTAL DISTURBED AREA

DISTURBED AREA = 59,971 SF = 1.38 ACRES

SITE SOIL CLASSIFICATION:

*CORNELIUS AND KINTON SILT LOAMS, 12 TO 20 PERCENT SLOPES * HYDROLOGIC SOIL GROUP C

RECEIVING WATER BODIES:

COLLECTED SITE RUNOFF: ONSITE DETENTION AND DISCHARGE TO PUBLIC STORM SYSTEM MAJOR DRAINAGE BASIN: JOHNSON CREEK RECEIVING WATERS: JOHNSON CREEK

RECEIVING WATER BODY WITH TMDL OR 303d FOR TURBIDITY OR SEDIMENTATION: NO

STANDARD EROSION AND SEDIMENT CONTROL PLAN DRAWING NOTES:

- ONCE KNOWN, INCLUDE A LIST OF ALL CONTRACTORS THAT WILL ENGAGE IN CONSTRUCTION ACTIVITIES ON SITE, AND THE AREAS OF THE SITE WHERE THE CONTRACTOR(S) WILL ENGAGE IN CONSTRUCTION ACTIVITIES. REVISE THE LIST AS APPROPRIATE UNTIL PERMIT COVERAGE IS TERMINATED (SECTION 4.4.C.I). IN ADDITION, INCLUDE A LIST OF ALL PERSONNEL (BY NAME AND POSITION) THAT ARE RESPONSIBLE FOR THE DESIGN, INSTALLATION AND MAINTENANCE OF STORMWATER CONTROL MEASURES (E.G. ESCP DEVELOPER, BMP INSTALLER (SEE SECTION 4.10), AS WELL AS THEIR INDIVIDUAL RESPONSIBILITIES. (SECTION 4.4.C.II)
- VISUAL MONITORING INSPECTION REPORTS MUST BE MADE IN ACCORDANCE WITH DEQ. 1200-C PERMIT REQUIREMENTS. (SECTION 6.5)
- 3. INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS. (SECTION 6.5.Q)
- 4. RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. (SECTION 4.7)
- 5. THE PERMIT REGISTRANT MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SECTIONS 4 AND 4.11)
- 6. THE ESCP MUST BE ACCURATE AND REFLECT SITE CONDITIONS. (SECTION 4.8)
- REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT WITHIN 10 DAYS. (SECTION 4.9)

SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP

- 8. SEQUENCE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (SECTION 2.2.2)
- CREATE SMOOTH SURFACES BETWEEN SOIL SURFACE AND EROSION AND SEDIMENT CONTROLS TO PREVENT STORMWATER FROM BYPASSING CONTROLS AND PONDING
- IDENTIFY, MARK, AND PROTECT (BY CONSTRUCTION FENCING OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED. IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS. (SECTION 2.2.1)
- 11. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED. (SECTION 2.2.5)
- 12. MAINTAIN AND DELINEATE ANY EXISTING NATURAL BUFFER WITHIN THE 50-FEET OF WATERS OF THE STATE. (SECTION 2.2.4)
- 13. INSTALL PERIMETER SEDIMENT CONTROL, INCLUDING STORM DRAIN INLET PROTECTION AS WELL AS ALL SEDIMENT BASINS, TRAPS, AND BARRIERS PRIOR TO LAND DISTURBANCE. (SECTIONS 2.1.3)
- 14. CONTROL BOTH PEAK FLOW RATES AND TOTAL STORMWATER VOLUME, TO MINIMIZE EROSION AT OUTLETS AND DOWNSTREAM CHANNELS AND STREAM BANKS. (SECTIONS 2.1.1. AND 2.2.16)
- 15. CONTROL SEDIMENT AS NEEDED ALONG THE SITE PERIMETER AND AT ALL OPERATIONAL INTERNAL STORM DRAIN INLETS AT ALL TIMES DURING CONSTRUCTION, BOTH INTERNALLY AND AT THE SITE BOUNDARY. (SECTIONS 2.2.6 AND 2.2.13)
- 16. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (SECTION 2.2.14)
- 17. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES. TEMPORARY OR PERMANENT STABILIZATIONS MEASURES ARE NOT REQUIRED FOR AREAS THAT ARE INTENDED TO BE LEFT UNVEGETATED, SUCH AS DIRT ACCESS ROADS OR UTILITY POLE PADS.(SECTIONS 2.2.20 AND 2.2.21)
- 18. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. (SECTION 2.3.7)
- 19. KEEP WASTE CONTAINER LIDS CLOSED WHEN NOT IN USE AND CLOSE LIDS AT THE END OF THE BUSINESS DAY FOR THOSE CONTAINERS THAT ARE ACTIVELY USED THROUGHOUT THE DAY. FOR WASTE CONTAINERS THAT DO NOT HAVE LIDS, PROVIDE EITHER (1) COVER (E.G., A TARP, PLASTIC SHEETING, TEMPORARY ROOF) TO PREVENT EXPOSURE OF WASTES TO PRECIPITATION, OR (2) A SIMILARLY EFFECTIVE MEANS DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS (E.G., SECONDARY CONTAINMENT). (SECTION
- 20. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPS SUCH AS: CONSTRUCTION ENTRANCE, GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND- DISTURBING ACTIVITIES. (SECTION 2.2.7)
- 21. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (SECTION 2.2.7.F)
- 22. CONTROL PROHIBITED DISCHARGES FROM LEAVING THE CONSTRUCTION SITE, I.E., CONCRETE WASH-OUT, WASTEWATER FROM CLEANOUT OF STUCCO, PAINT AND CURING COMPOUNDS. (SECTIONS 1.5 AND 2.3.9)
- 23. ENSURE THAT STEEP SLOPE AREAS WHERE CONSTRUCTION ACTIVITIES ARE NOT OCCURRING ARE NOT DISTURBED. (SECTION 2.2.10)
- 24. PREVENT SOIL COMPACTION IN AREAS WHERE POST-CONSTRUCTION INFILTRATION FACILITIES ARE TO BE INSTALLED. (SECTION 2.2.12)

ATTENTION EXCAVATORS:

OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CENTER. YOU MUST NOTIFY THE CENTER AT LEAST TWO BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. CALL 503-246-6699.

PERMITTEE'S SITE INSPECTOR: TBD COMPANY/AGENCY: xxxx PHONE: XXXX E-MAIL: xxxx DESCRIPTION OF EXPERIENCE: xxxx

SHEET INDEX

EROSION AND SEDIMENT CONTROL COVER SHEET

CLEARING AND DEMOLITION EROSION CONTROL PLAN

SITE AND UTILITY EROSION CONTROL PLAN VERTICAL CONSTRUCTION EROSION CONTROL PLAN

FINAL STABILIZATION PLAN **EROSION CONTROL DETAILS** 25. USE BMPS TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS; VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, FERTILIZER, PESTICIDES AND HERBICIDES, PAINTS.

SOLVENTS, CURING COMPOUNDS AND ADHESIVES FROM CONSTRUCTION OPERATIONS. (SECTIONS 2.2.15 AND 2.3) 26. PROVIDE PLANS FOR SEDIMENTATION BASINS THAT HAVE BEEN DESIGNED PER SECTION

2.2.17 AND STAMPED BY AN OREGON PROFESSIONAL ENGINEER. (SEE SECTION 2.2.17.A) 27. IF ENGINEERED SOILS ARE USED ON SITE, A SEDIMENTATION BASIN/IMPOUNDMENT MUST BE INSTALLED. (SEE SECTIONS 2.2.17 AND 2.2.18)

28. PROVIDE A DEWATERING PLAN FOR ACCUMULATED WATER FROM PRECIPITATION AND UNCONTAMINATED GROUNDWATER SEEPAGE DUE TO SHALLOW EXCAVATION ACTIVITIES. (SEE SECTION 2.4)

29. IMPLEMENT THE FOLLOWING BMPS WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (SECTION 2.3)

30. USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL. (SECTION 2.2.9)

31. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE. (SECTION 2.3.5)

32. IF AN ACTIVE TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED. SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM) SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN ENVIRONMENTAL MANAGEMENT PLAN APPROVAL FROM DEQ BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SECTION 1.2.9)

33. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR. (SECTION 2.2)

34. AS NEEDED BASED ON WEATHER CONDITIONS, AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPS MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS. (SECTION 2.2.8)

35. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (SECTION 2.1.5.B)

36. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT AND BEFORE BMP REMOVAL (SECTION 2.1.5.C)

37. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT, SEDIMENT BASINS AND SEDIMENT TRAPS; REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT. (SECTION 2.1.5.D)

38. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN-UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DEPARTMENT OF STATE LANDS REQUIRED TIMEFRAME. (SECTION 2.2.19.A)

39. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (SECTION 2.2.19)

40. 40. DOCUMENT ANY PORTION(S) OF THE SITE WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED OR WILL BE TEMPORARILY INACTIVE FOR 14 OR MORE CALENDAR DAYS. (SECTION 6.5.F.)

41. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR AN ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (SECTION 2.2.20)


42. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED, ALL TEMPORARY EROSION CONTROLS AND RETAINED SOILS MUST BE REMOVED AND DISPOSED OF PROPERLY, UNLESS NEEDED FOR LONG TERM USE FOLLOWING TERMINATION OF PERMIT COVERAGE.

RATIONALE STATEMENT

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMP's WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS, AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN, AN ACTION PLAN WILL BE SUBMITTED.

CONTRACTOR SHALL KEEP A RAIN GUAGE ONSITE OR REFERENCE THE ONLINE RAIN GUAGE 'CEDAR HILLS - KORPORTL262 AT HTTPS://WWW.WUNDERGROUND.COM/DASHBOARD/PWS/KORPORTL262


NO AMENDED SOILS ARE TO BE USED ONSITE



Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



PK21052 06.21.2023 Original Issue: Drawn/Check By BLU/EME

©2022 Baysinger Partners Architecture

PROPOSED PHASE 2 EROSION AND SEDIMENT

DESIGN REVIEW

Plotted: 10/4/23 at 1:58pm By: eeykelbosch

CONTROL COVER SHEET

PRE-CONSTRUCTION, CLEARING AND DEMOLITION NOTES:

- 1. ALL BASE ESC MEASURES (<u>INLET PROTECTION</u>, <u>PERIMETER SEDIMENT CONTROL</u>, <u>GRAVEL CONSTRUCTION ENTRANCES</u>, <u>ETC</u>.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- 2. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE <u>SEDIMENT FENCE</u>, <u>BERMS</u>
 <u>CONSTRUCTED OUT OF MULCH</u>, <u>CHIPPINGS</u>, <u>OR OTHER SUITABLE MATERIAL</u>, <u>STRAW</u>
 <u>WATTLES</u>, <u>OR OTHER APPROVED MATERIALS</u>.
- 3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
- 4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, <u>STREET SWEEPING</u>, <u>AND VACUUMING</u>, MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: STRAW WATTLES AND BIO BAGS.

SHEET NOTES

- 1. PROVIDE COMBINATION INLET PROTECTION AND BIOBAGS AT ALL CATCH BASINS AND STORM INLETS ONSITE.
- 2. PROVIDE INLET PROTECTION FILTER SACK ONLY AT ALL OFFSITE CATCH BASINS.

SHEET LEGEND


PROPERTY LINE


EX. CONTOUR MINOR

EX. CONTOUR MAJOR

EXTENT OF WORK

SEDIMENT CONTROL FENCE.
PLACE AT PROPERTY LINES, UNO (6.5)
(SHOWN OFFSET FOR CLARITY).











TREE TO BE REMOVED (UNDER SEPARATE DEMO PLAN)

PRE-DEVELOPED RUN-OFF IS COLLECTED IN A SERIES OF CATCH BASINS AND ROUTED OFFSITE INTO A PUBLIC STORMWATER SYSTEM. THE ENTIRE SITE IS TREATED IN A DOWNSTREAM SYSTEM.





Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





Well-crafted simplicity.


PETERKORT TOWNE SQUARE STARBUCKS



PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

PROPOSED PHASE
2 CLEARING AND
DEMOLITION
EROSION CONTROL

C6.1
DESIGN REVIEW



GRADING, SITE AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES

- 1. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:
 - A. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE RESTORATION PLAN FOR APPROPRIATE SEED MIX.
 - B. DWARF GRASS MIX (MIN. 100 LB./AC.)
 - 1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)
 - 2. CREEPING RED FESCUE (20% BY WEIGHT) C. STANDARD HEIGHT GRASS MIX (MIN. 100LB./AC.)
 - 1. ANNUAL RYEGRASS (40% BY WEIGHT)
 2. TURF-TYPE FESCUE (60% BY WEIGHT)
- 2. SLOPE TO RECEIVE TEMPORARY OR PERMANENT SEEDING SHALL HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN-OFF VELOCITY.
- 3. LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE.
- 4. TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.
- 5. STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION. STOCKPILES SHALL BE COVERED WITH PLASTIC SHEETING OR STRAW MULCH. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE.
- 6. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES. SLOPES EXCEEDING 25% MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES.

- 7. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.
- 8. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 9. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.
- 10. SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGE OF SEDIMENT AND SEDIMENT-LADEN WATER.
- 11. AN AREA SHALL BE PROVIDED FOR THE WASHING OUT OF CONCRETE TRUCKS IN A LOCATION THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERMS OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHES 50% OF THE CAPACITY.
- 12. SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH.
- 13. AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF INTO THE STORM WATER SYSTEM.

- 14. USE BMPs SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.
- 15. COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

- 1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- 2. STOCK PILE AREAS MAY BE MOVED AS NECESSARY TO ALLOW FOR CONSTRUCTION ACTIVITIES.
- 3. THE STAGING, EQUIPMENT MAINTENANCE, FUELING, PORT-A-POTTY, AND SOLID WASTE AREA MAY BE MOVED AS NECESSARY TO ALLOW FOR CONSTRUCTION ACTIVITIES.
- 4. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
- 5. LONG TERM SLOPE STABILIZATION MEASURES "INCLUDING MATTING" SHALL BE IN PLACE OVER ALL EXPOSED SOILS.
- 6. THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.
- 7. INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.


SHEET NOTES

- 1. CONTRACTOR SHALL PROVIDE A MINIMUM OF (1) 300
 GALLON CAPACITY 7'x7'x14" PORTABLE CONCRETE
 WASHOUT "ECO-PAN", OR APPROVED EQUAL. CONTACT R.T.
 CULLER AT (503) 209-3204. CONCRETE WASHOUT TO BE
 PICKED UP BY ECO-PAN AND RECYCLED OFF SITE. ADJUST
 LOCATION AS REQUIRED.
- 2. PROVIDE COMBINATION INLET PROTECTION AND BIOBAGS AT ALL CATCH BASINS AND STORM INLETS ONSITE.


(x) KEY NOTES

- 1 PROVIDE RIP-RAP PROTECTION AT OUTFALL
- 2 PROVIDE AREA FOR TEMPORARY SOIL STOCK PILE FROM EARTHWORK CUTTINGS REMOVED FROM SITE.
- 3 PROVIDE STAGING AREA FOR JOB TRAILERS, MATERIAL STAGING, AND PORTABLE RESTROOMS.

SHEET LEGEND



POST-DEVELOPMENT STORMWATER RUNOFF FROM THE PROPOSED DEVELOPMENT AREA IS COLLECTED VIA CATCH BASINS AND ROUTED THROUGH A WATER QUALITY FACILITY, UNDERGROUND CHAMBER DETENTION FACILITY, AND DISCHARGED OFFSITE INTO A PUBLIC STORMWATER SYSTEM. THE ENTIRE SITE IS TREATED IN A DOWNSTREAM SYSTEM.





Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS


Revisions

PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

PROPOSED PHASE
2 SITE AND UTILITY
EROSION CONTROL

PLAN

C6.2
DESIGN REVIEW



SW BARNES ROAD

EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

- 1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- 2. STOCK PILE AREAS MAY BE MOVED AS NECESSARY TO ALLOW FOR CONSTRUCTION ACTIVITIES.
- 3. THE STAGING, EQUIPMENT MAINTENANCE, FUELING, PORT-A-POTTY, AND SOLID WASTE AREA MAY BE MOVED AS NECESSARY TO ALLOW FOR CONSTRUCTION ACTIVITIES.
- 4. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
- 5. LONG TERM SLOPE STABILIZATION MEASURES "INCLUDING MATTING" SHALL BE IN PLACE OVER ALL EXPOSED SOILS.
- 6. THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.
- 7. INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.

SHEET NOTES

- 1. CONTRACTOR SHALL PROVIDE A MINIMUM OF (1) 300
 GALLON CAPACITY 7'x7'x14" PORTABLE CONCRETE
 WASHOUT "ECO-PAN", OR APPROVED EQUAL. CONTACT R.T.
 CULLER AT (503) 209-3204. CONCRETE WASHOUT TO BE
 PICKED UP BY ECO-PAN AND RECYCLED OFF SITE. ADJUST
 LOCATION AS REQUIRED.
- PROVIDE COMBINATION INLET PROTECTION AND BIOBAGS AT ALL CATCH BASINS AND STORM INLETS ONSITE.
- 3. VERTICAL CONSTRUCTION PHASE BASED ON COMPLETION OF SITE AND UTILITY PHASE.

× KEY NOTES

- 1 PROVIDE RIP-RAP PROTECTION AT OUTFALL
- 2 PROVIDE STAGING AREA FOR JOB TRAILERS, MATERIAL STAGING, AND PORTABLE RESTROOMS.

SHEET LEGEND

PROPERTY LINE

EXTENT OF WORK

SEDIMENT CONTROL FENCE.
PLACE AT PROPERTY LINES, UNO
(SHOWN OFFSET FOR CLARITY).

INLET PROTECTION (915)


BIO-BAG PROTECTION IN (845)
DITCHES, SWALES, WETLANDS (6.5)


STAGING AREA

SURFACE FLOW DIRECTION

CONCRETE WASHOUT

POST-DEVELOPMENT STORMWATER
RUNOFF FROM THE PROPOSED
DEVELOPMENT AREA IS COLLECTED VIA
CATCH BASINS AND ROUTED THROUGH
A WATER QUALITY FACILITY,
UNDERGROUND CHAMBER DETENTION
FACILITY, AND DISCHARGED OFFSITE
INTO A PUBLIC STORMWATER SYSTEM.
THE ENTIRE SITE IS TREATED IN A
DOWNSTREAM SYSTEM.





Baysinger

Baysinger Partners Architecture

2410 N. Lombard Street

Portand, OR 97217

503-546-1600



PETERKORT TOWNE SQUARE STARBUCKS

A Revision


PK21052


Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

© 2022 Baysinger Partners Architecture

PROPOSED PHASE 2 VERTICAL CONSTRUCTION EROSION CONTROL PLAN

C6.3
DESIGN REVIEW





Plotted: 10/4/23 at 1:59pm By: eeykelbosch

SHEET NOTES

- ALL EXPOSED SURFACES SHOULD BE PERMANENTLY STABILIZED PER LANDSCAPE PLANS. INCLUDES GROUND COVER, TREES, AND STANDARD SEEDING.
- 2. UPON COMPLETION OF PHASE ALL TEMPORARY EROSION CONTROL SHALL BE REMOVED. INCLUDES INLET PROTECTION AND SEDIMENT FENCE.

SHEET LEGEND

PROPERTY LINE

EXTENT OF WORK

CONCRETE SIDEWALK


HEAVY CONCRETE
PAVEMENT


STANDARD ASPHALT
PAVEMENT

LANDSCAPING

RAIN GARDEN

POST-DEVELOPMENT STORMWATER RUNOFF FROM THE PROPOSED DEVELOPMENT AREA IS COLLECTED VIA CATCH BASINS AND ROUTED THROUGH A WATER QUALITY FACILITY, UNDERGROUND CHAMBER DETENTION FACILITY, AND DISCHARGED OFFSITE INTO A PUBLIC STORMWATER SYSTEM. THE ENTIRE SITE IS TREATED IN A DOWNSTREAM SYSTEM.





Baysinger

Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE STARBUCKS



PK21052
Original Issue: 06.21.2023
Drawn/Check By: BLU/EME

PROPOSED PHASE
2 FINAL
STABILIZATION

STABILIZATION PLAN

C6.4
DESIGN REVIEW



THROUGH A SEDIMENT CONTROL BMP LIKE A FILTER BAG.

. ALL EXPOSED SOILS MUST BE COVERED DURING WET WEATHER PERIOD, OCTOBER 1, - MAY 31. 4. HOLD A PRECONSTRUCTION MEETING WITH PROJECT CONSTRUCTION PERSONAL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS.

RE-CONSTRUCTION, CLEARING, AND DEMOLITION NOTES . SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE, BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, STRAW WATTLES OR OTHER APPROVED MATERIALS.

. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL AND APPROVED IN AN INITIAL INSPECTION PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

. RUN-ON AND RUN-OFF SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.

RADING, STREET AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES

L. IF VEGETATED SEED MIXES ARE SPECIFIED, SEEDING MUST TAKE PLACE NO LATER THAN SEPTEMBER 1ST. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES, SEE RESTORATION PLAN FOR APPROPRIATE SEED MIX IN THOSE AREAS. SEED USED FOR TEMPORARY OR PERMANENT SEEDING OUTSIDE VEGETATED CORRIDORS SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:

A. DWARF GRASS MIX (MIN. 100 LB./AC.) 1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT) 2. CREEPING RED FESCUE (20% BY WEIGHT)

B. STANDARD HEIGHT GRASS MIX (MIN. 100LB.AC) 1. ANNUAL RYEGRASS (40% BY WEIGHT) 2. TURF--TYPE FESCUE (60% BY WEIGHT)

. SLOPE TO RECEIVE TEMPORARY OR PERMANENT SEEDING HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK--WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN--OFF VELOCITY.

. LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE.

TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.

. STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION. DURING "WET WEATHER" PERIODS, STOCKPILES SHALL BE COVERED WITH PLASTIC SHEETING OR STRAW MULCH. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE.

. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID--SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES. SLOPES EXCEEDING 25% MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES.

. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.

. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

. USE BMPS SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN--OFF FROM REACHING DISCHARGE POINTS. 10. COVER CATCH BASINS, MANHOLES AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACT COAT ETC. TO PREVENT PRODUCTS FROM ENTERING THE STORM SYSTEM.

ROSON AND SEDIMENT CONTROL BMP IMPLEMENTATION: . ALL SEDIMENT BARRIERS TO BE INSTALLED AFTER GRADING SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF

FINISHED GRADE AS SHOWN ON THESE PLANS. . LONG TERM SLOPE STABILIZATION MEASURES "INCLUDING MATTING" SHALL BE IN PLACE OVER ALL EXPOSED SOILS BY OCTOBER 1.

. THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.

4. INLET PROTECTION SHALL BE IN--PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.


STANDARD EROSION CONTROL NOTES FOR SITES 1 ACRE AND CleanWater Services


DRAWING NO. 946
























REVISED 10-31-19









Baysinger Partners Architecture 2410 N. Lombard Street Portand, OR 97217 503-546-1600 mattl@BaysingerPartners.com





PETERKORT TOWNE SQUARE **STARBUCKS**



PK21052 Original Issue: 06.21.2023 BLU/EME Drawn/Check By:

PROPOSED PHASE 2 EROSION CONTROL DETAILS

©2022 Baysinger Partners Architecture

C6.5 **DESIGN REVIEW**

RAWING NO. 900